

PROJECT: Emory Street Sanitary Sewer Rehabilitation

General Description: The scope of work consists of the removal and replacement of approximately 2,165 feet of existing 6-inch diameter sewer main and rehabilitation of approximately 5,240 ft of existing 6 and 8-inch sewer main with a cured-in-place pipe liner (CIPP). The project also includes several point repairs and the rehabilitation of 16 sanitary sewer man-holes.

Streets to be Impacted:

- Emory Street between Bascom Avenue and The Alameda
- Emerson Court between Emory Street and Naglee Avenue
- Morse Street between University Avenue and Naglee Avenue
- Park Avenue between University Avenue and Naglee Avenue.
- The project is within the vicinity of the Municipal Rose Garden, Rosecrucian Museum and Hoover Junior High School.

Cost: \$1.72 Million (Total Estimated Project Cost)

Schedule: June 2011 Anticipated Contract Award
September 2011 Construction Start

Project Photos:



Project Facts:

- The existing sanitary sewer in the area was installed in 1930s.
- Video inspection of the sewer pipes revealed broken pipes and lateral connections, root intrusion, joint offsets and sags which caused frequent maintenance operations by DOT.

Location Map

