

PROJECT: East San Jose Miscellaneous D.O.T. Rehabilitation

General Description: The scope of work consists of the rehabilitation of approximately 3,300 ft of 6-inch and 8-inch sanitary sewer mains with cured-in-place pipe (CIPP) liner and the removal and replacement of approximately 630 ft of 6-inch and 8-inch VCP. The project also includes several point repairs, sewer lateral repairs and rehabilitation of 17 sanitary sewer manholes.

Total Project Cost: \$644,400

Schedule: Project Award: 9/3/2010
Start Construction: 1/18/2011
Beneficial Use: 3/29/2011

Project Photo



A point repair being performed to replace a broken sewer pipe at Vista Verde Drive.

Project Quick Facts

- This project was developed in response to frequent sewer back-up incidents reported to DOT.
- Video inspection of the sewer pipes revealed sags, cracks, grease buildup, infiltration and root intrusions.
- The existing sewer pipe systems in these neighborhoods are more than 45 years old.
- The improvements in Panama Avenue are within the KONA SNI Area.
- The contractor for this project is Ranger Pipelines, Inc.

Location: The project is located in Panama Avenue, Vista Verde Drive, Cuesta Drive and Flint Avenue in East San Jose.

Location Map

