

## **PROJECT: Lariat Lane and Boulder Drive Sanitary Sewer Rehabilitation**

**General Description:** This project will reconstruct approximately 820 feet of 6-inch diameter vitrified clay pipe (VCP) and replace with 7-inch diameter high density polyethylene (HDPE) pipe. This sewer system passes through eight private properties within a Public Service Easement (PSE). In addition, the project will rehabilitate 1,830 feet of 6-inch sewer main with cured-in-place pipe liner.

The sanitary system in this area is over forty-five years old. The project was developed in response to frequent maintenance needs of the system due to root intrusion and offset pipe joints.

The project is located along Lariat Lane and within the PSE. To perform the improvement needed, the City's contractor may require additional working space in addition to the existing PSE area. The City will request permission from homeowners to enter portions of the private property during construction.

There will be minimal local traffic impacts during construction.

**Total Project Cost:** \$680,000

**Schedule:** Estimated Award: May 2011  
Estimated Construction Start: July 2011  
Estimated Completion: August 2011

## **Project Picture**



Along PSE



Along PSE

Location Map

