



- NOTE:**
1. AFTER THE COBBLESTONE HAS BEEN SET INTO THE MORTAR, THE EXCESSIVE MORTAR IN BETWEEN THE JOINTS OF THE COBBLESTONES SHALL BE CAREFULLY REMOVED AND RAKED IN A SMOOTH JOINT (NO PROTRUSION OF MORTAR WILL BE ALLOWED).
  2. SEAL FINAL SURFACE WITH WATER SEALER.

APPROVED BY  
*J. K. [Signature]*

DATE  
 4/10/14

**COBBLESTONE MEDIAN ISLAND**

DEPARTMENT OF PUBLIC WORKS



DRAWING NO.  
**R-21**